



15-095-30255 0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 21 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Jim Shipley of Graybol Oil Corporation has this date requested permission to plug the following described well:

Mr. Shipley guarantees payment of the plugging fee.

Operator's full Name: Graybol Oil Corporation

Complete Address: 2200 National Bank of Tulsa Bldg., Tulsa, Ok.

Lease Name: McKenna Well No. # 1

Location: C NW SE Sec. 3 Twp. 28 Rge. 8 (E)(W) W

County Kingman Total Depth 4395' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Shipley was instructed to plug the well as follows:

230' of 8 5/8" surface pipe, cement circulated with 185 sacks.

Fill hole with drilling mud to 200', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent