

15-095-01239-0000

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 6 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts.  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Percy Hall of Pickrell Drilling Co. has this  
 date requested permission to plug the following described well:

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 4th National Bank Bldg., Wichita, Kans.

Lease Name: Garlish Well No. # 1

Location: C NW NE Sec. 12 Twp. 28 Rge. 8 (E) (W) W

County Kingman Total Depth 4340 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Hall was instructed to plug the well as follows:

232' of 8 5/8" surface pipe, cement circulated with 170  
sacks. Fill hole with mud to 180', 1st cementing plug  
1/2 sack hulls, 20 sacks  
cement. Fill hole with mud to 40', 2nd cementing plug, 1/2  
sack hulls, cement with 10 sacks to base cellar. Rat hole  
bridged and cemented with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent