



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Kuhn of Graves Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Kuhn guarantees payment of the plugging fee.

Operator's full Name: Landes Exploration Co.

Complete Address: Box 867 Magnolia, Ark.

Lease Name: McPheeter Well No. 1

Location: C SW/SE/4 Sec. 13 Twp. 28s Rge. 8 (E)(W) W

County: Kingman Total Depth 44 46 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Kuhn was instructed to plug the well as follows:

231 ft of 8 5/8 surface pipe cemented with 190 sacks. Fill
hole to 230 ft, 1/2 sack hulls, plug, 25 sacks cement. Mud
to 40 ft, 1/2 sack hulls, Plug, 10 sacks cement to surface.
2 sacks cement in rat hole.

Very truly yours,

G. Russell Biberstein
Conservation Division Agent