

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 10 1967
7-10-67
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed June 20, 1967.

Dear Sir:

Mr. Webster Hill of Mack Oil Company has this
date requested permission to plug the following described well:

Mr. Hill guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas 67202

Lease Name: Clayton Well No. # 1

Location: C SW NE Sec. 4 Twp. 28 Rge. 10 (E)(W) W

County Kingman Total Depth 4433' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hill was instructed to plug the well as follows:

251' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill
hole with drilling mud to 250', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat & mouse holes with 4 sack

Very truly yours,

Arlene Elving
Conservation Division Agent