

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed June 20, 1967.

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1967
7-10-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mack Oil Company

Complete Address 812 Union Center Bldg., Wichita, Kansas 67202

Lease Name Clayton Well No. # 1

Location C SW NE Sec. 4 Twp. 28 Rge. 10 (E) (W)W

County Kingman Total Depth 4433'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Mack Oil Company

Address 812 Union Center, Wichita, Kansas 67202 License No.

Operation Completed: Hour 11:00 A.M. Day 5th Month July Year 1967

The above well was plugged as follows:

251' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole was
filled with drilling mud to 250', 1st cementing plug, bridged with 1 sack
of Gel-Mud and 1/2 sack of hulls, on fluid at 250', and cemented with 30
sacks, through the drill pipe. Hole was filled with drilling mud to 60',
bridged with 1/2 sack of Gel-Mud and 1/2 sack of hulls on fluid at 60', and
cemented with 25 sacks to the base of the cellar. Rat and mouse holes
bridged and cemented with 5 sacks.

This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7-10-67

INV. NO. 5539-W