

State of Kansas



15-047-20188-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSIONNOV 7 1975
11-7-75
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Norwood of DNB Drlg Co has this

date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.Operator's full Name: Sidwell Oil & Gas CoComplete Address: Box 2475 Pampa, TXLease Name: Burr Well No. 1Location: C NE/SE Sec. 19 Twp. 24s Rge. 20 (E)(W) WCounty: Edwards Total Depth 4750 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Norwood was instructed to plug the well as follows:368 ft 8 5/8 surface cemented with 225 sacks. Pump plug,35 sacks cement to 350 ft. Mud to 40 ft, plug, 1/2 sackhulls, 15 sacks cement to surface. 2 sacks cement inrat hole.Pumped by Allied Cementing Great Bend, KS

Very truly yours,

Conservation Division Agent