

15-155-19206-0000

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

August 31, 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this
date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Home-Stake Production Company

Complete Address: Box 68, Burrton, Kansas

Lease Name: Mary Collins Well No. W-16

Location: App. CNL N/2 SW Sec. 3 Twp. 24 Rge. 4 (X) (W) X

County Reno Total Depth 3374' Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3300' and cement with 3 sacks.

Fill hole with mud to 210'. Set rock bridge from 210' to 200' and

cement hole with 25 sacks. Fill hole with mud to 30'. Set rock

bridge from 30' to 20' and cap hole with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 14 1967

CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,


Conservation Division Agent