

R

State of Kansas



RECEIVED
AUG 31 1967

15-155-30087-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
Wichita, Kansas
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

8-31-67

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

August 21, 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Fred J. Ayesh

Complete Address: 438 Wetmore Drive, Wichita, Kansas 67209

Lease Name: Symms Well No. 1

Location: NE SW NE Sec. 3 Twp. 24 Rge. 4 (E) (W) X

County Reno Total Depth 3315' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

- Fill hole with sand to 3300' and cement with 5 sacks.
- Fill hole with mud to 210'. Set rock bridge from 210' to 200' and cement hole with 25 sacks. Fill hole with mud to 30'. Set rock bridge from 30' to 20' and cap hole with 10 sacks cement.

Very truly yours,

William J. Leonard
Conservation Division Agent