

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JOHN C. WOELK Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B HARVEY Secretary
 E. EDWARD JOHNSON Gen Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

December 23, 1965

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

JAN 11 1966

Dear Sir:

CONSERVATION DIVISION
 Wichita, Kansas

Mr. Steve Cowan of Flint Eng. & Constr. Co. has this

date requested permission to plug the following described well:

Mr. Cowan guarantees payment of the plugging fee.Operator's full Name: John MerrittComplete Address: P.O. Box 205, Haven, KansasLease Name: John Myers Well No. 8Location: C SW NW Sec. 3 Twp. 24 Rge. 4 (E) (W) XCounty Reno Total Depth 3398' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Cowan was instructed to plug the well as follows:

Push 8-5/8" plug to 3310'. Fill hole with sand to 3300' and
cement hole with 8 sacks. Fill hole with mud to 215'. Set
rock bridge from 215' to 200' and cement hole with 50 sacks.
Fill hole with mud to 35'. Set rock bridge from 35' to 25'
and cap hole with 25 sacks cement.

Very truly yours,

William J. Loman
 Conservation Division Agent