

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-047-21,154-0000

COUNTY Edwards

LEASE NAME 01iphant WELL# 1

SPOT LOCATION NE NW SW

SEC. 32 TWP. 24 RGE 20 (W)

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.
TYPE OR PRINT

LEASE OPERATOR Ladd Petroleum Corporation

PHONE # () 316-792-3571

OPERATORS LICENSE NO. 6029

CHARACTER OF WELL D&A (OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DATE WELL COMPLETED 2-22-84 PLUGGING COMMENCED 2-22-84

PLUGGING COMPLETED 2-22-84 REASON FOR ABANDONMENT OF WELL OR PRODUCING

FORMATION- Dry Hole

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City

IS ACO-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM T.D. 4800'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	640	8-5/8"	633'	None

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. 125 sks 60/40 Poz, 2% Gel, 3% CC:

50 sks @ 1440'

50 sks @ 690' By Allied

10 sks @ 40' Completed 2-22-84,

15 sks in rathole 9:30 a.m.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Allen Drilling Company LICENSE No. 5418

ADDRESS Box 1389, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON, SS.

John A. Johnson Agent
(EMPLOYEE OF OPERATOR) OR
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND
CORRECT. SO HELP ME GOD.

(SIGNATURE) John A. Johnson
(ADDRESS) Box 1389, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO BEFORE ME THIS 24 DAY OF February, 19 84

Wanda [Signature]
NOTARY PUBLIC


RECEIVED
STATE CORPORATION COMMISSION

MY COMMISSION EXPIRES: 12-10-87

MAR 20 1984

FORM CP-4
REVISED 06-83

CONSERVATION DIVISION
Wichita, Kansas



Side TWO

OPERATOR Ladd Petroleum Corporation LEASE NAME Oliphant SEC 32 TWP 24 RGE 20 (W)

WELL NO 1

FILL IN WELL INFORMATION AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
<p>Check if no Drill Stem Tests Run. <input checked="" type="checkbox"/> Check if samples sent Geological Survey.</p> <p>DST #1 4674-4738' Straddle 30-45-45-60 Stuck in hole, could not fish out. Well plugged with tool in hole.</p>			STOTLER	3405 (-1151)
			TOPEKA	3631 (-1377)
			HEEBNER	3996 (-1742)
			LANSING	4100 (-1846)
			KC	4184 (-1930)
			B/KC	4486 (-2232)
			CHEROKEE	4618 (-2364)
			MISSISSIPPI	4717 (-2463)
			LOGS	
			CDL-CNS	4796-2790'
		DIL-MSFL	4796-636'	

If additional space is needed use Page 2

Report of all strings set — surface, intermediate, production, etc.

CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Secks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	640'	60/40 Poz	275 sks	2% Gel, 3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Secks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Pecker set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity

Estimated Production—L.P.	Oil bbls.	Gas MCF	Water %	Gas-oil ratio bbls.	CFPB

Disposition of gas (vented, used on lease or sold)	Perforations