


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Edwards County, Sec. 33 Twp. 24S Rge. (E)20 (W)  
Location as "NE/CNW&SW" or footage from lines C/NE SE  
Lease Owner Thunderbird Drilling, Inc.  
Lease Name Heinz Well No. 1  
Office Address 4328 East Kellogg, Box 18407, Wichita, Kansas 67218  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 30 19 74  
Application for plugging filed April 30 19 74  
Application for plugging approved April 30 19 74  
Plugging commenced April 30 19 74  
Plugging completed April 30 19 74  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 10  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4700 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	530'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
Hole plugged as follows: Plugged at 550' with 50 sacks of 50-50 pozmix and 2% gel; plugged at 40' with 15 sacks of 50-50 pozmix and 2% gel. Plug down at 3:00 P. M. April 30, 1974.


RECEIVED  
STATE CORPORATION COMMISSION  
MAY 7 - 1974  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Strata Drilling Company  
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON ss.  
Kenneth J. Link (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link  
Kenneth J. Link  
P. O. Box 355, Great Bend, Kansas 67530  
(Address)

Subscribed and sworn to before me this 1st day of May, 1974.  
My commission expires December 14, 1977



Elaine H. Taylor  
Notary Public.

D R I L L E R S      L O G

#1 Heinz

CASING RECORD:  
525' of used 8-5/8"  
surface casing.

COMPANY: Thunderbird Drilling, Inc.

DESCRIPTION: C/NE SE  
Section 33-24S-20W  
Edwards County, Kansas

CONTRACTOR: Strata Drilling Company

TOTAL DEPTH:  
4700'

COMMENCED: April 19, 1974

COMPLETED: April 30, 1974

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	200	Ran 525' of used 8-5/8" surface casing; set and cemented at 530' with 290 sacks of common cement, 2% gel and 3% C. C. Plug down at 8:30 A. M. April 20, 1974.
Shale, Clay w/Sand Streaks	200	577	
Shale, Red Bed & Sand	577	1080	
Sand Streaks & Shale	1080	1707	
Shale	1707	2060	
Shale w/Lime Streaks	2060	2325	
Shale & Lime	2325	4095	
Lime	4095	4170	
Lime & Shale	4170	4595	
Lime	4595	4700	

ROTARY TOTAL DEPTH: 4700'

Ran electric log.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 7 - 1974  
CONSERVATION DIVISION  
Wichita, Kansas

D. & A.

Hole plugged as follows: Plugged at 550' with 50 sacks of 50-50 pozmix and 2% gel; plugged at 40' with 15 sacks of 50-50 pozmix and 2% gel. Plug down at 3:00 P. M. April 30, 1974.

STATE OF KANSAS )  
                          ) SS.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

*Kenneth J. Link*  
Kenneth J. Link

Subscribed and sworn to before me this 1st day of May, 1974.

My Commission Expires:

December 14, 1974

*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public

