


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Hodgeman County, Sec. 24 Twp. 24S Rge. (E) 21 (W)  
Location as "NE/CNW/WSW" or footage from lines C NE SW  
Lease Owner Rains & Williamson Oil Co.  
Lease Name SCHALLER Well No. 1  
Office Address 1425 Wichita Plaza, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 27 1964  
Application for plugging filed September 27 1964  
Application for plugging approved September 27 1964  
Plugging commenced September 27 1964  
Plugging completed September 27 1964  
Reason for abandonment of well or producing formation No oil or gas  
found in commercial quantities.  
If a producing well is abandoned, date of last production - - - 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott, Sublette, Kansas  
Producing formation - - - Depth to top - - - Bottom - - - Total Depth of Well 4852 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN  | PULLED OUT |
|-----------|---------|------|----|--------|---------|------------|
|           |         |      |    | 8-5/8" | 317.62' | None       |
|           |         |      |    |        |         |            |
|           |         |      |    |        |         |            |
|           |         |      |    |        |         |            |
|           |         |      |    |        |         |            |
|           |         |      |    |        |         |            |
|           |         |      |    |        |         |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from - - - feet to - - - feet for each plug set.

Plugged hole with 25 sacks @ 700'. Mud back to 300' and spot with 25 sacks cement. Mud back to 40'. Set plug & hulls and capped with 15 sacks cement. Plug down 12:15 p.m. 9-27-64.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 30 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rains & Williamson Oil Co.  
Address 1425 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Wilson Rains (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains  
Wilson Rains  
1425 Wichita Plaza, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 1964.

My commission expires January 8, 1968

Shirley Keck  
Shirley Keck Notary Public.

## ROTARY DRILLING LOG

Operator: Rains & Williamson Oil Co.  
 No. 1 Schaller  
 C NE SW Sec. 24-24S-21W  
 Hodgeman County, Kansas

Contractor: Rains & Williamson  
 Oil Co.  
 Commenced: 9-15-64  
 Completed: 9-27-64  
 Remarks: Set 317.62' of 8-5/8"  
 surface casing with  
 200 sacks GL3 cement.

## FORMATIONS:

|                      |       |
|----------------------|-------|
| Surface Clay         | 40'   |
| Sand                 | 73'   |
| Shale                | 515'  |
| Sand                 | 545'  |
| Shale & Red Bed      | 550'  |
| Shale                | 805'  |
| Anhydrite            | 820'  |
| Shale                | 910'  |
| Dakota Sand          | 1000' |
| Sand                 | 1180' |
| Shale & Red Bed      | 1417' |
| Anhydrite            | 1432' |
| Shale                | 1545' |
| Shale & Shells       | 2275' |
| Lime & Shale         | 2610' |
| Lime                 | 2940' |
| Lime & Shale         | 3395' |
| Shale & Lime         | 3835' |
| Lime & Shale         | 4225' |
| Lime                 | 4785' |
| Lime & Shale & Chert | 4785' |
| Lime & Chert         | 4852' |
| Total Depth (D&A)    | 4852' |

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 30 1964

CONSERVATION DIVISION  
 Wichita, Kansas

We certify the above log is true  
 and correct to the best of our  
 knowledge and belief.

RAINS & WILLIAMSON OIL CO.

*Wilson Rains*  
 Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the  
 State of Kansas, County of Sedgwick, this 29th day of September, 1964.

My Commission Expires:  
 January 8, 1968

*Shirley Keck*  
 Shirley Keck, Notary Public