

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Hodgeman County, Sec. 27 Twp. 24S Rge. 21W (E) (W)

Location as "NE/CNW/SW" or footage from lines. C-SW-SE
Lease Owner Sunray DX Oil Company
Lease Name W. F. Benish Well No. 1
Office Address 321 West Douglas, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 19
Application for plugging filed May 2, 1963
Application for plugging approved May 3, 1963
Plugging commenced May 1, 1963
Plugging completed May 1, 1963
Reason for abandonment of well or producing formation Non Commerical

NORTH

		X	

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Hugh Scott, Sublette, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4903 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lsg. Kansas City	Water	4099'	4396'	8 5/8"	250'	0'
Marmaton	Water	4491'	4590'			
Mississippi	Water	4706'	4905'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from total depth to 240' and placed 1/4 sack of hulls with 35 sacks of cement. Filled with heavy mud to 40' and placed 1/4 sack of hulls with 15 sacks of cement. Placed 5 sacks of cement in rat hole. Well Plugged and abandoned.

RECEIVED
STATE CORPORATION COMMISSION

MAY 8 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Stickle Drilling Company
Address 1100 Bitting Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Gary W. Pierce (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gary W. Pierce
321 West Douglas, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of May, 1963

My commission expires July 13, 1963

Wm Montgomery
Notary Public.

623-68

15-083-10274-0000

Sunray DX Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
May 6, 1963

Contractor: Stickle Drilling Company
Date Commenced: April 17, 1963
Date Completed: April 30, 1963

W. F. Benish No. 1
SW SE Sec. 27-24S-21W
Hodgeman County, Kans.

DRILLER'S LOG

Depth Figures Indicate Base of Formation:

Surface soil and clay	45
Sand	90
Shale	251
Shale and red bed	1190
Shale and shells	2135
Shale	2435
Shale and lime	2784
Lime and shale	2980
Shale and lime	3442
Shale	3675
Shale and lime	3956
Lime and shale	4007
Lime	4740
Lime and chert	4850
Chert and lime	4903 TD

I, Fred E. Stickle, hereby certify the above to be a true and complete Driller's Log for Sunray DX Oil Company's W. F. Benish No. 1 Well, SW SE Section 27-24S-21W, Hodgeman County, Kansas.

Fred E. Stickle
FRED E. STICKLE

M. J. Sensley
Notary Public

My Commission Expires January 11, 1967.

RECEIVED
STATE CORPORATION COMMISSION

MAY 8 1963

CONSERVATION DIVISION
Wichita, Kansas