

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Edwards

County. Sec. 28 Twp. 24S Rge. 20 (E) (W)

Location as "NE/CNW&SW" or footage from lines SW SW SW

Lease Owner Welch & Olsson Drilling Company, Inc.

Lease Name Haynes Well No. #1

Office Address 203 Rule Bldg. Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed: 10-29 19 55

Application for plugging filed 10-29 19 55

Application for plugging approved 10-29 19 55

Plugging commenced 10-29 19 55

Plugging completed 10-29 19 55

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4782 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 308' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded to 300'. Put gallon and half of hulls in sack and put in hole ahead of 20 sacks of cement thru drill pipe. Mudded to 35', and added 1/4th sack of hulls and cemented with ten sacks of cement

Name of Plugging Contractor Welch & Olsson Drilling Company, Inc. (If additional description is necessary, use BACK of this sheet)
Address 203 Rule Bldg. Wichita, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. E. Welch (Employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

203 Rule Bldg. Wichita, Ks.

(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of November, 19 55

My commission expires June 12, 1959

Notary Public.

PLUGGING
FILE SEC 28 T 24 R 20 W
BOOK PAGE 12 LINE 4

11-2-55
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG.

WELCH & OLSSON DRILLING COMPANY, INC.
 CONTRACTOR: WELCH & OLSSON DRILLING CO. INC.
 HAYNES #1
 SW SW SW 28-24S-20W, Edwards County, Kansas.

ELEVATION: 2243 R. B.
 Comm. Drlg: 10-14-55
 Compl. Drlg: 10-29-55
 Production: D & A.

Casing Record.

Set 308' of 8 5/8" with 200 sacks of cement.

(Figures indicated bottom of formations.)

| <u>FORMATIONS</u> | <u>DEPTHS.</u> |
|--------------------------------|----------------|
| Surface Clay & Sand: | 200 |
| Shale: | 700 |
| Sand: | 780 |
| Red Bed, Shale, Shells & Sand: | 1160 |
| Hard Sand: | 1325 |
| Shale: | 1408 |
| Anhydrite: | 1420 |
| Shale & Shells: | 1580 |
| Hard Sand: | 1760 |
| Shale & Shells: | 2220 |
| Shale W/Lime Streaks: | 2390 |
| Shale & Shells W/Lime Strks: | 2470 |
| Lime & Shale: | 2817 |
| Shale & Lime: | 2985 |
| Lime & Shale: | 3300 |
| Shale W/Broken Lime Strks: | 3450 |
| Lime & Shale: | 3615 |
| Lime: | 3755 |
| Lime: | 4695 |
| Cherty Lime: | 4715 |
| Chert: | 4782 T. D. |

STATE OF KANSAS,)
) SS:
 SEDGWICK COUNTY,)

I hereby certify that the above is a true and correct copy of Drillers Log of Well drilled in the SW SW SW of Section 28, Township 24 South, Range 20 West, Pawnee County, Kansas.

WELCH & OLSSON DRILLING COMPANY, INC.
 BY *R. E. Welch*
 R. E. WELCH

Subscribed and sworn to before me this 1st day of November, 1955.

Seesh Sibley
 Notary Public.

My commission expires:
 June 12, 1959

PLUGGING
 FILE REC 28 Y 24 R 20W
 BOOK PAGE 12 LINE 4

RECORDED
 STATE COMMISSION
 NOV - 2 1955
 CONSERVATION DIVISION
 Wichita, Kansas