

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1982
CONSERVATION DIVISION
Wichita Kansas 4-21-82

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Reno SEC. 3 TWP. 24S RGE. 4W E/W
Location as in quarters or footage from lines:
NE SE NE

Locate Well
correctly on above
Section Platt.

Lease Owner Charles D. Johnson, P.O. Box 278, McPherson, Ks. 67460
Lease Name Rimbey Well No. 1
Office Address P.O. Box 278, McPherson, Kansas 67460
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed April 16, 1982
Application for plugging filed _____
Plugging commenced _____
Plugging completed April 16, 1982
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman, Holyrood, Ks.

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Sand</u>		<u>0</u>	<u>175'</u>	<u>12 3/4"</u>	<u>175'</u>	<u>None</u>
<u>Shale</u>		<u>175'</u>	<u>280'</u>	<u>12 3/4"</u>	<u>105'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Set plug with 75 sacks of cement. Top plug at 40' with 32 sacks of cement,
10 sacks in rathole. Plugging completed at 3:30 A. M., by State Pluggger
Gilbert Toman, Holyrood, Kansas. Halliburton did the plugging. Plugging
completed April 16, 1982.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Blackstone Drilling, Inc.
Box 1184, McPherson, Kansas 67460

STATE OF Kansas COUNTY OF McPherson, ss.

Charles D. Johnson (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.


(Signature)

P.O. Box 278, McPherson, Kansas 67460
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of April, 19 82

Juanita M. Flood
Notary Public.

My Commission expires:





A Division of Halliburton Company
DUNCAN, OKLAHOMA 73538

BULK MATERIALS DELIVERY AND TICKET CONTINUATION

15-155-20867-0000

FOR INVOICE AND
TICKET NO. 415954

DATE 4-15-82	CUSTOMER ORDER NO.	WELL NO. AND FARM # 1 Rimbey	COUNTY Harvey	STATE Ks.
CHARGE TO Charles D. Johnson		OWNER Same	CONTRACTOR Blackstone Drilling No. B 115080	
MAILING ADDRESS 523 W. Kansas		DELIVERED FROM Eldorado, Ks..	LOCATION CODE 50305	PREPARED BY McElhiney
CITY & STATE McPherson, Ks. 67460		DELIVERED TO Location	TRUCK NO. 0513	RECEIVED BY GEOFF SHAFER

PRICE REFERENCE	SECONDARY REF. OR PART NO.	CODE		DESCRIPTION	UNITS 1		UNITS 2		UNIT PRICE	AMOUNT	
		L	D		QTY.	MEAS.	QTY.	MEAS.			
504-043		1	B	Regular Portland	117	Sk.			4.85	567.	45
THIS IS NOT AN INVOICE											
				Returned Mileage Charge							
				TOTAL WEIGHT							
				LOADED MILES							
				TON MILES							
				SERVICE CHARGE ON MATERIALS RETURNED							
500-207				SERVICE CHARGE				117	.95	111.	15
500-306				Mileage Charge	11,998						
				TOTAL WEIGHT							
				LOADED MILES	78						
				TON MILES	467.922				.70	327.	55
No. B 115080				CARRY FORWARD TO INVOICE							
				SUB-TOTAL						1,006.	15



Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250
McPHERSON, KANSAS 67460
April 16, 1982

COMPANY: CHARLES D. JOHNSON
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: RIMBEY #1
LOCATION: NE SE NE Section 3-24S-4W,
Reno County, Kansas
COMMENCED: April 9, 1982
COMPLETED: April 16, 1982
ELEVATION:

0	to	175	Sand
175	to	490	Shale
490	to	600	Anhydrite
600	to	840	Shale & Lime
840	to	1800	Lime & Shale
1800	to	2075	Shale & Lime
2075	to	2295	Lime & Shale
2295	to	2550	Shale & Lime
2550	to	2985	Lime
2985	to	3249	Lime & Shale
3249	to	3277	Shale & Lime
3277	to	3375	Mississippi T. D.

Cut 17" hole to 265' and run 267' of 12 3/4" casing, cemented with 225 sacks of cement at 265'. Plug down at 11:30 A. M., April 9, 1982. Hole dry and abandoned. Set plug with 75 sacks of cement. Top plug at 40' with 32 sacks of cement, 10 sacks in rathole. Plugging completed at 3:30 A. M., Gilbert Toman, State Plugger, Holyrood, Kansas, April 16, 1982. Halliburton did the plugging.

TOPS:

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your RimbeY #1, located on the NE SE NE Section 3-24S-4W, Reno County, Kansas as reflected by the files of Blackstone Drilling, Inc.


P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 19th day of April, 1982.


Johnnie L. Schmidt - Notary Public

