

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-155-02881-0000

API NUMBER _____ Completion 3/35

LEASE NAME Myers

WELL NUMBER 1

_____ Ft. from S Section Line

_____ Ft. from E Section Line

SEC. 3 TWP. 24 RGE. 4W (E) or (W)

COUNTY Reno

Date Well Completed _____

Plugging Commenced 2-17-94

Plugging Completed 3-10-94

TYPE OR PRINT
NOTICE: Fill out complotoly
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Brigman Productions Inc.

ADDRESS 2518 Lundman Dr., Hutchinson, KS 67502

PHONE# (316) 665-8479 OPERATORS LICENSE NO. 6891

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3603'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	3600'	none
				7	3400'	839'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Sanded bottom @ 3350' & dumped 8 sks cement. Well was parted 2 jts down, pulled those 2 jts. Tore down, moved off location. 3-7-94 Moved in again. Shot @ 839', ran spear down casing, speared 7" casing & pulled it out. Welder cut hole in surface pipe, shot @ 660', ran 1" tubing to 660', pumped 45 sks cement. Pulled tubing out, shot @ 350', pumped 230 sks cement to surface.
(If additional description is necessary, use BACK of this form.)

(OVER)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brigman Productions Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 17th day of March, 1994

[Signature]
Notary Public

My Commission Expires:



CS-4
05-08

Ran 1" tubing down back side to 210', pumped 165 sks cement to surface. Ran 1" tubing down 8 5/8 to 350', pumped 100 sks cement to surface. 60/40 poz. Plugging complete.

