

2 090055

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-21,280-0000

SWSW, SEC. 24 1/2, T. 28 S, R. 9 W/E

660 feet from 1/10 section line

4620 feet from 1/2 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6236

Lease Name Merten D. Well # 1

Operator: MTM Petroleum

County Kingman

Name & Address Box 82

Well Total Depth 4470 145.28 feet

Spivey, Ks. 67142

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 301'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Medicine Lodge, Ks.

Company to plug at: Hour: 11:00a.m. Day: 2 Month: 10 Year: 19 84

Plugging proposal received from _____

(company name) _____ (phone) _____

were: Bottom plug-sand back to 4050'

Top plug-2 sacks hulls, 6GELL, 1 sack of hulls, 125 sacks of cement

Plugging Proposal Received by _____

(TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part _____ None _____

Operations Completed: Hour: 12:00p.m. Day: 2 Month: 10 Year: 19 84

ACTUAL PLUGGING REPORT The bottom of the hole was filled with sand to 4050' and 4

sacks of cement spotted on top of sand. The pipe was shot off and 2897' of

4 1/2" was recovered. The top was plugged by pumping 2 sacks of hulls, 6 sacks of

GEL, a sack of hulls and 125 sacks of common cement to surface. Instant shut-in

pressure was 200.

RECEIVED STATE CORPORATION COMMISSION

10-09-84 OCT 9 1984

Remarks: Allied Ticket #38467

(If additional description is necessary, use BACK of this form)

CONSERVATION DIVISION Wichita, Kansas

VIOLATED (date) observe this plugging.

Signed David [Signature] (TECHNICIAN)

DATE 10-15-84

INV. NO. 4316

FORM CP-2/3 Rev. 01-84