

11-25-88

2 010181

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-20,990-00-00

SW NW SW, SEC. 33, T 28 S, R 9 W/EX
1650 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7062

Lease Name Mervin Eck Well # 1

Operator: Kenner Oil Company

County Kingman 145.24

Name & Address 320 S. Boston

Well Total Depth 4469 feet

Tulsa, OK 74103

Conductor Pipe: Size _____ feet

Surface Casing: Size 8-5/8 feet 218'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30p Day: 25 Month: 11 Year: 19 88

Plugging proposal received from Darrel Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 3 sx hulls - 35 sx cement @ 4100' - 25 sx gel - 105 sx 60/40 poz 4% at 400' to surface.

Plugging Proposal Received by Warren Kirkpatrick (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: _____ Day: 25 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT Pulled 3600' of 4-1/2" - pumped 3 hulls with 35 sx & plug - then 25 gel & plug - then 105 sx 60/40 4% gel from 400' to surface - Allied #5212

SI 100# PSI - Max 300# PSI

RECEIVED
STATE CORPORATION COMMISSION
1-27-88
JUN 23 1988

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
XXXXX did not observe this plugging.

Signed Warren Kirkpatrick (TECHNICIAN)

DATE 6-23-89

INV. NO. 25117
11-25-88

2 100448

11-9

API NUMBER 15- 095-20,990-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NW SW, SEC. 33, T 28 S, R 9 WAK
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7062
Operator: Keener Oil Co.
Name & Address: 320 S. Boston
Tulsa, OK 74103
918-587-4154

Lease Name Mervin Eck Well # 1
County Kingman 145.24
Well Total Depth 4469 feet
~~XXXXXX~~ Pipe: Size 4-1/2" feet 4466; /150 SX
Surface Casing: Size 8-5/8" feet 218' /175 SX

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____ Perf 4175'-82' 4457'-69'

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347 Chase, KS 67524

Company to plug at: Hour: 3:00p Day: 9 Month: 11 Year: 19 88

Plugging proposal received from Darryl Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

work: Sand to 50' above perf - 4 sx cement w/dump bailer - shoot & pull pipe -
pump 3 hulls, 35 sx cement - space with 12 gal and 100 sx of cement.

Plugging Proposal Received by Sanders
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 4:00p Day: 9 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT Bottomed with sand to 4175' & dumped 4 sx cement w/bailer -
shot 3631' & 3418' & pulled 3418' of 4-1/2" - pumped 3 sx hulls, 35 sx cement,
spaced with 25 sx gel - plugged and 105 sx of 60/40 4% gel for surface & salt
plug

STATE CORPORATION COMMISSION
1-4-89
JAN 04 1989

Remarks: Howco #009022 60/40 4% gel
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 1-9-89
INV. NO. 23559

observe this plugging.
WC

Signed Johnny L Sanders
(TECHNICIAN)