

11-19

RECEIVED
KANSAS CORPORATION COMMISSION

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

DEC 06 1993

CONSERVATION DIVISION
WICHITA, KS

^{w/2}
API NUMBER: 15-095-20,334-0000
SW SW SW, SECTION 16 TOWNSHIP 28 RANGE 9W

OPERATOR LICENSE # 6236 660 FEET FROM S SECTION LINE
4950 FEET FROM E SECTION LINE

OPERATOR MTM
NAME & P O BOX 82
ADDRESS SPIVEY, KS 67142

LEASE NAME: MERTENS A # 1
COUNTY: KINGMAN
WELL TOTAL DEPTH: 4470' 145.28

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 302'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: CLARK
ADDRESS: MEDICINE LODGE KS LICENSE: 5105

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 19 MONTH: 11 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: MORGENSTERN
COMPANY NAME: _____ PHONE: _____

WERE: SAND TO 4300' & 4 SX - 30 SX @ 1400' - 30 SX @ 900' -
350' TO SURFACE

PLUGGING PROPOSAL RECEIVED BY: STEVE VAN GIESON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)

COMPLETED: HOUR: 1:00 DAY: 19 MONTH: 11 YEAR: 1993

ACTUAL PLUGGING REPORT:
SANDED BOTTOM TO 4300' & 4 SX OF COMMON - SHOT OFF
4-1/2" @ 3500' - PULLED TO 1400' & PUMPED 30 SX -
PULLED TO TO 900' & PUMPED 30 SX - PULLED TO 350' AND
CIRC CMT TO SURF - CMT CIRC TOO SOON - PULLED REST OF
CSG & FOUND MOST OF IT FULL OF HOLES - RAN TUB BACK TO
350' & CIRC CMT TO SURF

REMARKS: ALLIED #3720 60/40 4%

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 12-9-93

INV. NO. 39442

151

Jack Luthi (AGENT)