

11-22

RECEIVED
KANSAS CORPORATION COMMISSION

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

DEC 10 1993

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-095-20,330-0000

C SW SE, SECTION 17 TOWNSHIP 28 RANGE 9W

OPERATOR LICENSE # 6236

660 FEET FROM S SECTION LINE
1980 FEET FROM E SECTION LINE

OPERATOR MTM PETROLEUM INC
NAME & P O BOX 82
ADDRESS SPIVEY KS 67142

LEASE NAME: ALBRITTEN #1
COUNTY: KINGMAN
WELL TOTAL DEPTH: 4465' 145.11

PIPE: _____

SURFACE CASING: 8-5/8" @ 270'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: CLARKE CORP
ADDRESS: MEDICINE LODGE KS LICENSE: 5105

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: JEFF STILLETTO
COMPANY NAME: CLARKE CORP PHONE: _____

WERE: 5-1/2" @ 4463' - PERFS 4369-74' - SAND BACK TO 4320'
& 5 SX - SHOOT PIPE & PULL & SPOT 35 SX @ 1400', 35 SX
@ 900' & CIRC CMT 320' TO SURF

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART () NONE (_____)

COMPLETED: HOUR: 1730 DAY: 22 MONTH: 11 YEAR: 1993

ACTUAL PLUGGING REPORT:
PERFS COVERED W/SAND TO 4320 & CAPPED W/5 SX CMT -
5-1/2" RECOVERED FROM 3250' & PULLED TO 1414' & 35 SX
CMT SPOTTED THRU CSG - CSG PULLED TO 913' & 35 SX CMT
SPOTTED - CSG PULLED TO 320' & CMT CIRC TO SURF -
REMAINING CSG PULLED OUT & CMT BROUGHT BACK TO SURF

REMARKS: ALLIED CMT #3629 60/40 4% GEL

INVOICED
DATE DEC 12 1993
INV. NO. 39492

131
STEVE VAN GIESON (AGENT)