

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER:

15
12-095-21759-0000
NW

C-SE/4 SECTION 36 TOWNSHIP 28 RANGE 8 W

12-5-12-10 N

OPERATOR LICENSE # 8740

1320 FEET FROM S SECTION LINE

OPERATOR Bramwell Petroleum

1320 FEET FROM E SECTION LINE

NAME 15183 SW 25th Ave.

ADDRESS Spivey, KS 67142

LEASE NAME: Southwest College #2

COUNTY Kingman

WELL TOTAL DEPTH: 4130

PIPE:

SURFACE CASING 8 5/8 210'

134.23

1/9

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD _____ D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Duke Drilling Co.

ADDRESS: Wichita KS. LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: _____

PLUGGING PROPOSAL RECEIVED FROM: John Armbruster

COMPANY NAME: Duke Drilling PHONE: _____

WERE: 35 sks @ 1350'

35 sks @ 750'

35 sks @ 260'

25 sks @ 60'

15 sks @ RH 10 sks @ MH

PLUGGING PROPOSAL RECEIVED BY: District 2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE (xx)

COMPLETED: HOUR: 0600 DAY: 9 MONTH: 1 YEAR: 2000

ACTUAL PLUGGING REPORT: Drill pipe was run in the hole open end to 1350' where 35 sks of cement was spotted. The drill pipe was pulled to 750' where 35 sks of cement was spotted. The drill pipe was pulled to 260' where 35 sks of cement was spotted. The drill pipe was pulled to 60' where cement was circulated to surface. The Rat hole was circulated with 15 sacks of cement. The Mouse hole was circulated with 10 sks of cement.

REMARKS: United cementing 60/40 Poz 4 % gel

RECEIVED
KANSAS CORPORATION COMMISSION

APR 17 2000

CONSERVATION DIVISION
WICHITA, KS

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

Steve VanGieson

DATE 4/18/00
06/607

FORM CP-2/3
REV. 3/90

R