

2 040181

-0001

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION (NE) NE, SEC. 26, T 28 S, R 8 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-095-20021-A  
4620 feet from N/S section line  
660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9533  
Operator: Fairchild Exploration  
Name & Address Bob Fairchild  
RR3  
Kingman Ks. 67068

Lease Name Martha Simon Well # 1  
County Kingman 138.42  
Well Total Depth 4259 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address Box 176 Chase Ks.

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Bob Fairchild  
(company name) Fairchild Exp. (phone) \_\_\_\_\_

were: 4 1/2 4250 150 sks. 35sx to 3700 4-1-85  
Perfs. 4129-31 4 hulls 15 gel

APR - 1 1985

Plugging Proposal Received by Don T. Steve VG.  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1230 Day: 28 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Sun Cementing squeezed the perforations off by pumping 35 sacks of cement to 3700'. Kelso came in and shot and pulled 3480' of 4 1/2" casing. Sun Cementing came back in and pumped to top off by squeezing thru the 8 5/8" casing, 4 sacks of hull 15 sacks of gel and 150 common cement.

Remarks: Sun Cementing Ticket # 206687 MX500 # SI 300 #  
(Additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.

DATE 4-4-85

Signed Steve VG.  
(TECHNICIAN)

INV. NO. 7546

RP