

7-20-87

2 100241

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-20,514 - 0000
SE, SEC. 26, T 28 S, R 8 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 7062

Operator: Keener Oil Co.
Name & Address 320 S. Boston #406
Tulsa, OK 74103
(918) 587-4154

feet from S section line
feet from E section line

Lease Name Art Simons Well # 1

County Kingman 133.80

Well Total Depth 4117 feet

Conductor Pipe: Size 4 1/2" feet 4112' w/150 sxs

Surface Casing: Size 8 5/8 feet 208 w.100 sxs

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____ Open Hole _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Chase, KS 67524

Company to plug at: Hour: 10:30 Day: 20 Month: 7 Year: 1987

Plugging proposal received from _____

(company name) Kelso Casing Pulling (phone) _____

were: Sand bottom to 4050' and dump 5 sxs cement. Shoot and pull 5 1/2". Pump through 8 5/8" 300 obs hulls, 12 sxs gel and 100 sxs of cement.

Plugging Proposal Received by Warren Kirkpatrick (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45 Day: 20 Month: 7 Year: 1987

ACTUAL PLUGGING REPORT Sanded bottom to 4050' and dumped 5 sxs cement. Shot and pulled 100 joints of 5 1/2" totalling 3300', pump through 8 5/8" 300 lbs hulls, 12 sxs gel and 100 sxs of cement.

RECEIVED STATE CORPORATION COMMISSION

JUL 29 1987 7-29-87

CONSERVATION DIVISION Wichita, Kansas

Remarks: Allied Cementing 60/40 poz, 4% gel (if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Johnny Sanders (TECHNICIAN)

DATE 7-29-87

INV. NO. 17646