

2030334

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-155-20,937-0000

E/2 SW, SEC. 34, T 23 S, R 4 W/4

1980' feet from N/S section line

2970' feet from N/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5280 - # 8110

Lease Name Rimhey A Well # 1

Operator: Ziebert + Wedel

County Reno 118.37

Name & Address 1136 Wheeler, Box 785

Well Total Depth 3642' 3505' feet

McPherson, Ks. 67460

~~Casing~~ Pipe: Size 5 1/2" feet 3505'

Surface Casing: Size 13 3/8" feet 266'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Ks. 67524

Company to plug at: Hour: 14:00 Day: 13 Month: 12 Year: 19 85

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: Prof. 3347' to 3361' Sand hole to 3300', dump 6 ex cent, shoot + pull 5 1/2" casing, pump 3 ex hells, 15 ex gel. 160 ex cent. down 13 3/8" surface casing.

Plugging Proposal Received by Dist # 2  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 16:45 Day: 13 Month: 12 Year: 19 85

ACTUAL PLUGGING REPORT Sanded hole to 3300' dumped 6 ex cent.

with bailer, shot and pulled 2547' of 5 1/2" casing.

Halliburton Services #099813-X pumped 3 ex hells,

15 ex gel, 160 ex 60/40 Permiox cent. down 13 3/8" surface

casing. Pump Press 250 # S.I.P. 75 #

Remarks: Top Plug RECEIVED 1-6-86  
(If additional description necessary, use BACK of this form.)

INVOICED  
DATE 1-7-86  
INV. NO. 11873

W

JAN 6 1986  
Signed Don Thompson  
CONSERVATION DIVISION (TECHNICIAN)  
Wichita, Kansas

RO