

2-20

2-070683

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-155-20,851-0000

NW NE NW, SECTION 34 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 4419 4950 FEET FROM S SECTION LINE
OPERATOR BEAR PETROLEUM INC. 3430 FEET FROM E SECTION LINE
NAME & BOX 438
ADDRESS HAYSVILLE, KS 67060
LEASE NAME: GRABER #7
COUNTY: RENO
WELL TOTAL DEPTH: 3403' 110.59
PIPE: 5 1/2" @ 3399'
SURFACE CASING: 10 3/4" @ 203'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: GRESSEL OIL FIELD SERVICES

ADDRESS: BOX 607, BURRTON, KS 67020 LICENSE: 3009

COMPANY TO PLUG AT: HOUR: 9:30 DAY: 19 MONTH: 2 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: EDDIE GRESSEL

COMPANY NAME: GRESSEL OIL FIELD SERVICES PHONE: (316) 463-5261

WERE: SAND TO 3290' AND 5 SACKS OF COMMON
PERF 575' AND 35 SACKS
PERF 250' AND CIRCULATE

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 10:00 DAY: 20 MONTH: 2 YEAR: 1997

ACTUAL PLUGGING REPORT: DUMPED 55 GALLONS OF SAND, COULD NOT GET BAILER DOWN HOLE TO DUMP CEMENT, RAN TUBING TO BOTTOM, PUMPED 10 SACKS. PERF AT 575', PUMPED 35 SACKS THRU TUBING. WAITED 1 HOUR AND TAGGED CEMENT AT 507', PULLED TUBING, SWEDGED 5 1/2" AND PUMPED 50 SACKS. CAME BACK NEXT MORNING. NO CEMENT OVER THE PERFS AT 250'. GOT SLIPS OUT OF HEAD SO WE COULD RUN 1" DOWN BACK SIDE, PUMPED 50 SACKS DOWN 5 1/2". RUNNING 1" DOWN BACK SIDE TO 250', PUMPED 35 SACKS. WAITED 45 MINUTES, PUMPED 35 SACKS; WAITED 30 MINUTES, PUMPED 25 SACKS, WAITED, FOUND CEMENT TRUCK WAS EMPTY. GOT MORE CEMENT. PUMPED 50 SACKS OF CEMENT TO SURFACE. THEN IT STARTED TO FALL. PULLED 1" OUT AND LET SET. RAN 1" DOWN 5 1/2". PUMPED ANOTHER 25 SACKS TO SURFACE, TOPPED OFF. SURFACE PIPE WITH 3 SACKS. CEMENT STAYED.

REMARKS: 60/40 POZ 4% GEL 340 SACKS CEMENT UNITED 2/19 #3035, 2/20 #3036

RECEIVED
FEB 28 1997
KANSAS CORPORATION COMMISSION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.
Jack Luthi
JACK LUTHI

INVOICED
DATE MAR 03 1997
INV. NO. 47679
2-20