

1 070204

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,256-0000SE SE, SEC. 22, T 24 S, R 21 W660 feet from S section line660 feet from E section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 4704Lease Name Wells Well # 44-22Operator: True Oil CompanyCounty Hodgeman 156.00

Name &amp;

Address P.O. Box 2360Well Total Depth 4800 Mississippi feetCasper, WY 82602

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 505Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor True Drilling Company License Number 4708Address P.O. Drawer 2360, Casper, WY 82602Company to plug at: Hour: 5:20 pm Day: 4 Month: August Year: 1986Plugging proposal received from Buzz Montgomery(company name) True Drlg. (phone) (307) 237-9301Elevation 2300'were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1453'1st plug at 1460' with 50 sx cement2nd plug at 560' with 50 sx cement3rd plug at 40-0' with 10 sx cement4th plug to circulate the rat hole with 15 sx cement5th plug to circulate the mouse hole with 10 sx cementPlugging Proposal Received by Dan Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_Operations Completed: Hour: 8:30 pm Day: 4 Month: August Year: 1986ACTUAL PLUGGING REPORT 1st plug at 1463 with 50 sx cement, 2nd plug at 560' with 50 sxcement, 3rd plug from 40' to surface with 10 sx cement, 4th plug to circulate rathole with 15 sx cement and 5th plug to circulate the mouse hole with 10 sx cement.8-7-86Remarks: Used 60/40 Pozmix with 6% gel pumped by Halliburton.AUG 7 1986

(If additional description is necessary, use BACK of this form.)

I (the undersigned) observe this plugging.

Signed Dan Goodrow

(TECHNICIAN)

DATE 8-7-86INV. NO. 14675