

2-8-88

1 030914

API NUMBER 15-083-21,296-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NW SE, SEC. 27, T 24 S, R 21 W/E
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5104

Lease Name Benish Well # 1

Operator: Blue Goose Drilling Company, Inc.
Name & Address: P.O. Box 1413
Great Bend, KS 67530

County: Hodgeman 154.05
Well Total Depth 4740 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 221

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Blue Goose Drilling Company, Inc. License Number 5104

Address P.O. Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 11 p.m. Day: 7 Month: 2 Year: 19 88

Plugging proposal received from Martin Miller

(company name) Blue Goose Drilling Company, Inc. (phone) 316-792-5633

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1429-41'
1st plug at 1440' with 50 sx cement, 2nd plug at 740' with 80 sx cement,
3rd plug at 240' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:30 a.m. Day: 8 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1440' with 50 sx cement,
2nd plug at 740' with 80 sx cement,
3rd plug at 240' with 40 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

2-10-88

STATE CORPORATION COMMISSION

FEB 10 1988

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 2-12-88

Signed Steve Durrant (TECHNICIAN)

INV NO. 19827
2-8