

To: 1 100051  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT 6-10

Operator License / 3988

Operator: Slawson Exploration Co., Inc.

Name & Address 200 N. Harvey, #1412

Oklahoma City, OK 73102

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allen Drilling Co. License Number 5418

Address P.O. Box 1389, Great Bend, KS 67530-1389

Company to plug at: Hour: 6 a.m. Day: 10 Month: 6 Year: 19 96

Plugging proposal received from Vince Schrappel

(company name) Allen Drilling Co. (phone) 316-793-5681

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1442' with 50 sx cement, 2nd plug at 920' with 50 sx cement, **RECEIVED**

3rd plug at 690' with 50 sx cement, 4th plug at 40' with 10 sx cement, **6-18-96**

5th plug to circulate rathole with 15 sx cement, **JUN 18 1996**

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Gary Winters  
**CONSERVATION DIVISION WICHITA, KS (TECHNICIAN)**

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 1 p.m. Day: 10 Month: 6 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 1442' with 50 sx cement,

2nd plug at 920' with 50 sx cement,

3rd plug at 690' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

**INVOICED**  
(I  did not observe this plugging.)

DATE 6-25-96

INV. NO. 45873  
6-10

Signed Gary Winters  
(TECHNICIAN)

EFFECTIVE DATE: 6-3-96

State of Kansas

15-083-21,435-0000

FORM MUST BE SIGNED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL

ALL BLANKS MUST BE FILLED

SGA7... Yes...  No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 6 15 96  
month day year

Spot \_\_\_\_\_ East  
C...- SW...- NE. Sec 35.. Twp 24S. S, Rg 21...  West

OPERATOR: License # 3988  
Name: Slawson Exploration Co., Inc.  
Address: 200 N. Harvey, #1412  
City/State/Zip: OKC OK 73102  
Contact Person: Steve Slawson  
Phone: (405) 232-0201

1980 feet from South (North) line of Section  
1980 feet from East / West line of Section  
IS SECTION  REGULAR \_\_\_\_\_ IRREGULARY

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Hodgeman  
Lease Name: Hermann Well #: M #1  
Field Name: Wildcat

CONTRACTOR: License #: 5418  
Name: Allen Drilg.

Is this a Prorated/Spaced Field? ... yes  no  
Target Formation(s): Mississippi/Cherokee/LKC

Nearest lease or unit boundary: 1980  
Ground Surface Elevation: 2290 feet MSL

Well Drilled For: Well Class: Type Equipment:  
 Oil ... Enh Rec ... Infield  Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWWO ... Disposal  Wildcat ... Cable  
... Seismic: ... # of Holes ... Other  
... Other

Water well within one-quarter mile: ... yes  no  
Public water supply well within one mile: ... yes  no

Depth to bottom of fresh water: 120' 180'  
Depth to bottom of usable water: 600' 580'

Surface Pipe by Alternate:  1 ... 2  
Length of Surface Pipe Planned to be set: 620'

Length of Conductor pipe required: \_\_\_\_\_  
Projected Total Depth: 4900'

Formation at Total Depth: Mississippi  
Water Source for Drilling Operations:

If OWWO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

OUR Permit #: APPLY TO DWR FOR PERMIT  
Will Cores Be Taken?: ... yes  no

Directional, Deviated or Horizontal wellbore? ... yes  no  
If yes, true vertical depth: \_\_\_\_\_

If yes, proposed zone: \_\_\_\_\_  
580' Alt. I Reg. ANSAS CORPORATION COMMISSION

Bottom Hole Location: \_\_\_\_\_

Exp. 11/28/96

AFFIDAVIT

The undersigned hereby affirms that all information furnished herein is true and correct.

JUN 18 1996

CONSERVATION DIVISION  
WICHITA, KS

Pusher Vertical  
SPUD DATE 5/21 / INIT. JK  
LENGTH SURFACE PLANNED 600  
RESERVE PIT STATUS- REMOVE FLUID \_\_\_\_\_ LINED \_\_\_\_\_  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y \_\_\_\_\_ N \_\_\_\_\_ SIZE HOLE \_\_\_\_\_  
SURFACE PIPE 2 1/2 @ 670 CONDUCTOR \_\_\_\_\_  
ANHYDRITE T- B- \_\_\_\_\_ ELEVATION \_\_\_\_\_  
TD 4800 FORMATION MISS.  
RAN PIPE @ \_\_\_\_\_ DV TOOL \_\_\_\_\_ ALT II DONE \_\_\_\_\_  
SX Y N  
Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Plug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Anhydrite Base @ 1442 Ft. W/ 50 SX  
1/2 Base Anyh. @ 920 Ft. W/ 50 SX  
1/2, 1/2 Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Bottom Surface @ 1420 Ft. W/ 50 SX  
40' Plug @ 40 Ft. W/ 0 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 0 SX  
WATER WELL 40 SX (Irr. Well) Pond \_\_\_\_\_  
Hauling \_\_\_\_\_  
TECHNICIAN GLE DATE 6-2-96  
TYPE OF CEMENT 60/40 PER. 120 44'  
STARTING TIME 6:00 (AM/PM) DATE 6-10-96  
COMPLETION TIME / : (AM/PM) DATE 6-10-96  
CEMENT COMPANY Attila Halibut