

CONSERVATION DIVISION
WICHITA, KANSAS

7-22-86
2 100033

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-155-02885-0000

NW/4 SEC. 3, T. 24 S, R. 4 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7376

Lease Name J. Meyer Well # 5

Operator: Merrit Oil Company

County Reno 117.75

Name & Address 315 E. Eisenhower, Suite 117

Plug back XXXX Total Depth 3368 3623' feet

An Harbor, Michigan 48104

Conductor Pipe: Size _____ feet

Surface Casing: Size 1 1/2 feet 600

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Merrit Oil Company License Number 7376

Address _____

Company to plug at: Hour: 10:30 Day: 15 Month: 7 Year: 19 85

Plugging proposal received from Joe Pit

(company name) _____ (phone) _____

were: 7 1/2" collapsed at 423'--run 2" to 423' and pump well full to surface

Plugging Proposal Received by S. Van Gieson JK
(TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part _____ None _____

Operations Completed: Hour: 3:45 Day: 15 Month: 7 Year: 19 85

ACTUAL PLUGGING REPORT Ran 2" to 423 feet and pumped 75 sacks of common, 2%cc, no gel, 3 sacks of hulls. Pulled 10 joints and let set up. Ran tubing 15 feet from first plug, pumped 300 sacks, 60/40 poz, 2% gel, 1 sack of hulls and filled to surface.

Remarks: Howco Ticket #099-293-7
(If additional description is necessary, use BACK of this form.)

INVOICED

(did not observe this plugging.)

DATE 7-26-85

Signed J. L. Sanderson
(TECHNICIAN)

INV. NO. 9131

WC
AUG 2 1 1985 SEP 2 5 1985 OCT 2 5 1985

DEC 1 2 1985

FORM CP-2/3
Rev. 01-84

7-15