

To: 1 120081
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-14-88
API NUMBER 15-185-21,217-0000

NE NE SW, SEC. 33, T 24 S, R 14 W/EX
2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4635
Operator: Great Bend Casing Pullers
Name & Address: P.O. Box 768
Great Bend, KS 67530

Lease Name Ralph Waters Well # 1-C
County Stafford 141.60
Well Total Depth 4357 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635
Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1:15 p.m. Day: 14 Month: 3 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" casing (no record) Perfs at 4154-85, 4185-4230'

1st plug sand back to 4100' and dump 4 sx cement on top of sand through bailer,
2nd plug pump into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10
sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 p.m. Day: 14 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4100' and dump 4 sx cement
on top of sand through bailer.

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement. 3-17-88

Welded plate on 8 5/8" - bad threads.

Pumping pressure 0-700 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% bel by Allied. Recovered 3018' of 4 1/2" casing. Top of plug @ 30'.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

MAR 17 1988
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
(If desired, please observe this plugging.)

Signed Duane Rankin (TECHNICIAN)

DATE 3-21-88

INV. NO. 20140