

3-14-88

To: 1 120083  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-21,014-0000  
C NE SE, SEC. 33, T 24 S, R 14 W/E  
1980 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4635  
Operator: Great Bend Casing Pullers  
Name & Address: P.O. Box 768  
Great Bend, KS 67530

Lease Name H.J. Waters Well # 1 B  
County Stafford 141.38  
Well Total Depth 4350 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 413

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers License Number 4635  
Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 14 Month: 3 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" casing (no record) PBD 4320' Perfs at 3710-3700'

1st plug sand back to 3650' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump into 8 5/8" casing with 400 lbs., 10 sx gel, 50 sx cement, 10 sx gel,  
100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 a.m. Day: 14 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3650' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2149' of 4 1/2" casing. Top of plug @ 40'  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 3-21-88  
INV. NO. 20141

(operator) observe this plugging.

Signed Duane Rankin (TECHNICIAN)  
CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

MAR 17 1988