

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 100'S NW NE SW Sec. 27, T 24 S, R 12 W/XX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,291-0000

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5230

Lease Name Budde Well # 1

Operator: Petroleum Energy, Inc.
Name & Suite 415, First Nat'l Bank Bldg.
Address Wichita, KS 67202

County Stafford

Well Total Depth 4100 feet 133.25

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 13 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO James Ray

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: PBDT 3700 Perfs 3656 - 60 4 1/2 set at 4099

1st plug sanded back to 3600 and dumped 4 sx cement on top of sand

2nd plug squeezed through head with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel,

1 sack hulls and released 8 5/8" rubber plug and pumped an additional 125 sx cement.

Maximum pressure 300# and shut-in pressure 100#

Signed Steve Quimant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:45 pm Day: 13 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug sanded back to 3600' and dumped 4 sx cement on top

of sand. 2nd plug squeezed through head with 3 sx hulls, 10 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls and released 8 5/8" rubber plug and pumped an additional

125 sx cement. Maximum pressure 300# and shut-in pressure 100#.

PBDT 3700 Perfs 3656-60 4 1/2 set at 4099

Remarks: Use 60/40 Pozmix 2% gel 3% cc. by Allied They recovered 2000' 4 1/2"
production casing.

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as here stated
and that I (did / did not) observe this plugging.

Signed Steve Quimant
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 2-22-84

INV. NO. 0896