

1 120649
TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-25
API NUMBER 15- 185-21,583-0000 182
NW SW NE, SEC. 27, T 24 S, R 12 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 6988
Operator: Smith Oil Operations
Name & Address: P.O. Box 550
Hutchinson, KS 67504-0550

3630 feet from S section line
2310 feet from E section line
Lease Name Reed Well # 1
County Stafford 134.87
Well Total Depth 4150 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well Gas Well _____ Input Well _____ SHD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 25 Month: 11 Year: 19 91

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4131' w/150 sx cement, PBTD 4070', Perfs at 3531'
1st plug sand back to 3500' and dump 5 sx cement on top of sand through bailer,
2nd plug pump into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 4:30 p.m. Day: 25 Month: 11 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3480' and dumped 5 sx cement on top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement. RECEIVED
Pumping pressure 0-500 psi and shut in 300 psi. STATE CORPORATION COMMISSION

DEC 03 1991

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1800' of 5 1/2" casing
(if additional description is necessary, use BACK of this form.) WICHITA, KANSAS

INVOICED
DATE 12-9-91
INV. NO. 34061

Signed Duane Rankin (TECHNICIAN)