

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-069-20375-01-00  
Spot: SESWSWSW Sec/Twnshp/Rge: 15-26S-29W  
196 feet from S Section Line, 4764 feet from E Section Line  
Lease Name: MILLERSHASKI 2629 Well #: 1-15H  
County: GRAY Total Vertical Depth: 5429 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4813		WITH 50 SX CMT
COND	20	120		WITH 10 SX CMT
	11 7	5429	1632	WITH 250 SX CMT
PROD	4.5	9346	0	WITH 450 SX CMT
SURF	9.625	1580		WITH 590 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/11/2016 2:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 4813' WITH 50 SX CMT. PLUG AT 1620' WITH 75 SX CMT. PLUG AT 960' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: PARTIAL  
Date/Time Plugging Completed: 05/12/2016 10:30 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 4813' WITH 50 SX CMT. 1ST PLUG AT 1620' WITH 80 SX CMT. SDON. 5/12/16: TAG CMT AT 1419'. 2ND PLUG PULL TBG TO 960' & PUMP 50 SX CMT. POOH. 3RD PLUG TOP OFF 60' TO SURFACE WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
8614	8837		
8211	8468		
7823	8097		
7456	7712		
7088	7324		
6686	6937		
5941	9200		
3288	3573		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED  
MAY 13 2016  
KCC DODGE CITY

Signed Tony A. Davis ECR5  
(TECHNICIAN)  
KCC WICHITA  
MAY 18 2016

No  
5-18-16

RECEIVED