

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-069-20391-01-00  
Spot: SESWSWSW Sec/Twnshp/Rge: 28-26S-29W  
208 feet from S Section Line, 551 feet from W Section Line  
Lease Name: MINET 2629 Well #: 1-33H  
County: GRAY Total Vertical Depth: 5006 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	130		WITH 16 SX CMT
	11 4.5	9737		WITH 300 SX CMT
PROD	7	5499	1720	WITH 300 SX CMT
SURF	9.625	1575		WITH 540 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/27/2016 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: ROYCE Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/02/2016 10:30 AM KCC Agent: KEN JEHLIK

**Actual Plugging Report:**

4/27/16: FOUND 2 7/8" TBG & ESP STUCK. ATTEMPT TO FREE AT 70000#. NO MOVEMENT. RAN FREE POINT. 100% FREE AT 2250'. 100% STUCK AT 3000'. TAGGED FILL UP ON TOP OF ESP AT 4865'. PERFORATE 4 HOLES IN THE 2 7/8" TBG AT 4865'. INJECTION RATE 3 BPM AT 400#. GOT CIRCULATION UP 2 7/8" X 7" ANNULUS. WORK TBG STILL STUCK. PUMP 50 SX CMT DOWN TBG. DISPLACE WITH 10 BBLs WATER & TBG PRESSURE TO 2500#. CMT LACK 7 BBLs OF GETTING TO THE PERFS. REVERSE OUT CMT. SUSPECT A TBG LEAK AT 2100'. ALSO A CASING LEAK IN THE 7" AT 1600'. 4/28/16: RAN FREE POINT TOOL. COULD NOT GET PAST 1770'. CUT TBG OFF AT 1764' & TOO H WITH TBG & CABLE. LEFT APPROX. 3100' OF 2 7/8" TBG & ESP PUMP IN HOLE. CUT 7" CASING AT 1720' & START TOO H. 4/29/16: TOO H WITH REMAINING 7" CASING & RAN 2 7/8" TBG TO 1732'. SPOT 150 SX CMT PLUG. FULL RETURNS. 5/2/16: TAG TOC @ 1395'. PULL TO 900' & SPOT 60 SX CMT. FULL CIRCULATION. PUMP 20 SX CMT AT 64'.

**Perfs:**

Top	Bot	Thru	Comments
8443	8765		
8048	8372		
7663	7972		
7266	7590		
6860	7184		
6448	6770		
6083	6385		
5668	5992		
5240	9600		

Remarks: \*\*COMPLAINCE ISSUE: DENIED TA HIGH FL\*\* USED CLASS A COMMON CEMENT BY ORR ENTERPRISES. TMD = 9755'.

Plugged through: TBG

District: 01

Signed

(TECHNICIAN)

RECEIVED  
MAY - 2 2016  
KCC DODGE CITY

KCC WICHITA  
MAY 18 2016  
RECEIVED

20  
5-18-16