

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-069-20430-01-00  
Spot: NWNEENW Sec/Twnshp/Rge: 33-27S-29W  
200 feet from N Section Line, 2240 feet from W Section Line  
Lease Name: YOST 2729 Well #: 1-33H  
County: GRAY Total Vertical Depth: 5110 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5050		WITH 20 SX CMT
COND	20	130		WITH 14 SX CMT
	11 4.5	9033		WITH 580 SX CMT
PROD	7	5535	1606	WITH 325 SX CMT
SURF	9.625	1570		WITH 610 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/05/2016 8:30 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Revd. from: ROYCE Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: See attached proposed plugging procedure. POOH w/rods and pump. TOO H w tbg. Set CIBP @ 5050' and Cap w/20 sks cement. Mix and spot 40 sks Class C Cement @ 1800'. Mix and spot 60 sks Class C Cement @ 1600'. Mix and spot 60 sks Class C Cement at 850'. Mix and spot 20 sks cement at 64' to 4'. Cut and cap well. Dig up rig anchors. Subject to KCC District Staff approval and additional additions to procedure.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/05/2016 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5050' WITH 20 SX CMT. CUT 7" CASING AT 1820'. NOT FREE. CUT CASING AT 1606' & POOH. RAN TBG TO 1820' INSIDE THE 7" CASING & SPOT 125 SX CMT. FULL CIRCULATION. WAIT 2 HOURS & TAG CMT PLUG AT 1595'. RUN TBG TO 1565' & SPOT 40 SX CMT. FULL CIRCULATION. PLUG AT 850' WITH 70 SX CMT. PLUG AT 64' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
8568	8894		
8312	8502		
8078	8265		
7638	7794		
7422	7590		
7240	7374		
7028	7190		
6841	8894		
6441	6990		
4850	8012		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED CLASS A CEMENT BY ORR ENTERPRISES. TMD = 9033'.

Plugged through: TBG

District: 01

RECEIVED  
MAY 11 2016  
KCC DODGE CITY

Signed Ken Jehlik  
KCC WICHITA (TECHNICIAN)  
5/A

720  
5-18-16

MAY 18 2016

RECEIVED