

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-079-20026-00-00  
Spot: SWSENW Sec/Twnshp/Rge: 35-23S-2E  
2730 feet from S Section Line, 3390 feet from E Section Line  
Lease Name: BALZER C Well #: 1  
County: HARVEY Total Vertical Depth: 2850 feet

Operator License No.: 33608  
Op Name: W.D. SHORT OIL CO., LLC  
Address: 102 S RIVER RD PO BOX 729  
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4	2849		
PROD	4.5	2850		100 SX
SURF	8.625	180		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/28/2016 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Revd. from: MIKE ANSTINE Company: W.D. SHORT OIL CO., LLC. Phone: (620) 218-1822

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/28/2016 12:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) RAN IN HOLE TO TD W/TUBING, PULLED UP TO APPROX. 2830'. 2) PUMPED 25 SKS OF 60/40/4% CEMENT W/ 1 SK HULLS THROUGH TUBING. 3) PULLED TUBING UP TO APPROX. 260', CIRCULATED OIL OUT W/WATER (FLUID CALCULATED TO DISPLACE OIL AFTER TUBING REMOVED INDICATED BOTTOM PLUG WAS SET.) 4) PUMPED 20 SKS OF 60/40/4% CEMENT, NO ADDITIVES THROUGH TUBING AND CIRCULATED TO SURFACE. 5) PULLED TUBING OUT, CEMENT APPROX. 5' DOWN IN WELL AND REMAINING AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
2764	2768	CSG	

Remarks: CEMENTING COMPELTED BY ELITE CEMENTING & ACIDIZING, EUREKA, KS. TICKET #2772

Plugged through: TBG

District: 02

Signed Jonathan Hill  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

MAY 13 2016

CONSERVATION DIVISION  
WICHITA, KS

218-18-16

JK