

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-20761-00-00
Spot: E2SWNW Sec/Twnshp/Rge: 34-18S-24W
3292 feet from S Section Line, 4181 feet from E Section Line
Lease Name: CROWELL Well #: 4
County: NESS Total Vertical Depth: 4366 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		900		
PROD	5.5	4352	0	WITH 150 SX CMT
SURF	8.625	246		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/05/2016 8:30 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: MORRIS SMITH Company: TRANSPACIFIC OIL Phone: (316) 262-3596

Proposed Plugging Method: RUN TBG TO BOTTOM WITH 50 SX CMT & 200# HULLS. PERFORATE AT 1600' & PUMP 50 SX CMT & 100# HULLS. SET CIBP OR 50 SX COMMON CMT 3% CC @ 900'. LOAD HOLE & LOG. PERFORATE AT TOP OF CMT. PUMP 80 SX CMT OVER CASING VOLUME. 100 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/05/2016 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4345' & PUMP 50 SX CMT & 200# HULLS. PULL TBG & PERFORATE AT 1600' & SPOT 50 SX CMT. PULL TBG & SET CIBP @ 900'. TEST CASING & THEN LOG HOLE. FOUND CMT AT 650'. PERFORATED AT 600'. RAN TBG TO 880' & PUMPED 105 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & PUMPED 60 SX CMT DONW CASING. CMT CIRCULATED OUT BACKSIDE.

Perfs:

Top	Bot	Thru	Comments
4352	4374		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED
MAY 10 2016
KCC DODGE CITY

Signed Michael Maier
51A (TECHNICIAN)

70
5-18-16