

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-10619-00-02
Spot: SWNESW Sec/Twnshp/Rge: 29-26S-12W
1657 feet from S Section Line, 3453 feet from E Section Line
Lease Name: STUEDERA Well #: 2
County: PRATT Total Vertical Depth: 4077 feet

Operator License No.: 9232
Op Name: TIMBERLINE OIL & GAS CORPORATIO
Address: 4000 PENROSE PLACE
RAPID CITY, SD 57702

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1610		WITH 25 SX CMT
CIBP		4077		
PROD	5.5	4290	1530	WITH 150 SX CMT
SURF	8.625	865		WITH 350 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 04/05/2016 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: BRANT GROTE Company: TIMBERLINE OIL & GAS Phone: (620) 672-8240

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/05/2016 1:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

****UNABLE TO GET BELOW 1722' INSIDE 5 1/2" CASING. SUSPECT CASING PARTED OR COLLAPSED.** SET CIBP @ 1610' & SPOT 25 SX CMT ON TOP OF CIBP THROUGH TBG. 1ST PLUG AT 885' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 297' WITH 50 SX CMT. 3RD PLUG AT 66' WITH 40 SX CMT.**

Perfs:

Top	Bot	Thru	Comments
4054	4059		
3802	3891		
3222	3335		
3130	3134		

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: TBG

District: 01

RECEIVED
APR 21 2016
KCC DODGE CITY

Signed Stephen J. Pfeifer
SA (TECHNICIAN)

no
5-18-16