

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21464-00-00
Spot: SESE Sec/Twnshp/Rge: 31-30S-19W
659 feet from S Section Line, 650 feet from E Section Line
Lease Name: HUNT Well #: 31-2
County: KIOWA Total Vertical Depth: 5300 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5013		WITH 10 SX CMT
COND	20	75		
PROD	4.5	5297	1273	WITH 185 SX CMT
SURF	8.625	657		WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/10/2016 1:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 5013' WITH 2 SX CMT. PLUG AT 1230' WITH 50 SX CMT. PLUG AT 690' WITH 50 SX CMT. PLUG AT 330' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/10/2016 3:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5013' WITH 10 SX CMT ON TOP OF CIBP. 1ST PLUG AT 1250' WITH 50 SX CMT. 2ND PLUG AT 750' WITH 50 SX CMT. 3RD PLUG AT 330' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5128	5134		
5104	5120		
5078	5080		
5063	5068		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
MAY 12 2016
KCC DODGE CITY

Signed [Signature]
(TECHNICIAN)

KCC WICHITA

MAY 18 2016

RECEIVED

720
5-18-16