

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-00921-00-00  
Spot: NWNW Sec/Twnshp/Rge: 10-32S-10W  
4620 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: LONG Well #: 1  
County: BARBER Total Vertical Depth: 4450 feet

Operator License No.: 5123  
Op Name: PICKRELL DRILLING COMPANY, INC.  
Address: 100 S MAIN STE 505  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4020		WITH 2 SX CMT
PROD	4.5	4449	0	WITH 100 SX CMT
SURF	8.625	200		WITH 100 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/11/2016 2:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: 700' TO SURFACE CIRCULATE CMT TO SURFACE WITH HULLS.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE  
Date/Time Plugging Completed: 05/11/2016 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

\*\*SQUEEZED AT 500' & CIRCULATED TO SURFACE WITH CMT & HULLS\*\* SET CIBP @ 4020' & 2 SX CMT. RAN TBG TO 700'. PUMPED 75 SX CMT WITH 100# HULLS TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4354	4380		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: TBG

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
MAY 16 2016  
KCC DODGE CITY

KCC WICHITA  
MAY 18 2016  
RECEIVED

Form CP-2/3  
no  
5-18-16