

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-147-20113-00-00
Spot: NWNENW Sec/Twnshp/Rge: 20-4S-18W
330 feet from N Section Line, 1650 feet from W Section Line
Lease Name: E. JACKSON Well #: 11
County: PHILLIPS Total Vertical Depth: 3350 feet

Operator License No.: 5252
Op Name: R. P. NIXON OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3350		125 SX
SURF	8.625	210		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/06/2016 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DUANE ATCHERBURG Company: R.P. NIXON OPERATIONS INC. Phone: (785) 628-3834

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/800 # hulls.
Production perforations: 3125' - 3257'
Casing leak at 1220' - 1225'
Squeeze at 900' - 933' w/200 sx cement.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/06/2016 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 1460' and 600'. Ran tubing to 3100' and pumped 110 sx cement w/300 # hulls.
Pulled tubing to 1500' and pumped 125 sx cement w/200 # hulls to circulate cement to surface.
Pulled all tubing. Hooked to 4 1/2" casing and pumped 40 sx cement to circulate 8 5/8" x 4 1/2" annulus and top off 4 1/2" casing.

GPS: 39.69697N -099.37827W

Perfs:

Top	Bot	Thru	Comments
3255	3257		
3218	3224		
3208	3210		
3200	3204		
3183	3185		
3164	3168		
3125	3129		

Remarks: GLOBAL CEMENTING TICKET # 2605

Plugged through: TBG

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

MAY 09 2016

MAY 13 2016

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

no
5-18-16