

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-20387-00-00
Spot: NWNENW Sec/Twnshp/Rge: 22-32S-10W
4972 feet from S Section Line, 3644 feet from E Section Line
Lease Name: ECK V Well #: 1-22
County: BARBER Total Vertical Depth: 4395 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 124 N MAIN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2712		WITH 2 SX CMT
CIBP		4322		
PROD	5.5	4395	0	WITH 100 SX CMT
SURF	8.625	239		WITH 235 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/10/2016 9:00 AM
Plug Co. License No.: 30346 Plug Co. Name: SHAWNEE WELL SERVICE, INC.
Proposal Rcvd. from: JEFF CAPPS Company: SHAWNEE WELL SERVICE Phone: (620) 254-7893

Proposed Plugging Method: CIBP @ 4322' WITH 2 SX CMT. CIBP @ 2712' WITH 2 SX CMT. PERFORATE AT 600'-0'.

Plugging Proposal Received By: WADE KLAUS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/10/2016 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP'S @ 4322' & 2712' WITH 2 SX CMT ON TOP OF EACH CIBP. (CIBP WAS SET AT 2712' TO ISOLATE CASING LEAKS AT 2812-2843'.) PERFORATE 5 1/2" CASING AT 600'. PUMP DOWN 5 1/2" CASING WITH 175 SX CMT FILLING 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS WITH CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4372	4392		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
MAY 11 2016
KCC DODGE CITY

5A
KCC WICHITA
MAY 18 2016
RECEIVED

Form CP-2/3
20
5-18-16