


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above Section Plat

Kingman County, Sec. 9 Twp. 28S Rge. 9 ~~XX~~/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW/4 SE/4

Lease Owner Keener Oil Company
Lease Name Wilson Well No. 1
Office Address 320 S. Boston, Suite 406, Tulsa, OK 74103
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole

Date Well completed 3/08 19 83
Application for plugging filed 3/08 19 83
Application for plugging approved 3/08 19 83
Plugging commenced 3/08 19 83
Plugging completed 3/08 19 83

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Maurice Leslie
Producing formation Depth to top Bottom Total Depth of Well
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Total Depth 4324 feet. Set first plug at 1150 feet with 40 sacks of common cement, 3% Calcium Chloride and 2% Gel; set second plug at 240 feet with 40 sacks; 10 sacks and a bridge at 40 feet and 10 sacks in the rathole. Job completed at 8:45 p.m. on 3/08/83.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kaw Drilling Co., Inc.


STATE OF KANSAS COUNTY OF SEDGWICK, ss. contractor
K. S. Martin, President of Kaw Drilling Co., Inc. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. S. Martin
K. S. Martin, President 1010 Union Center
(Address) Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 11th day of March, 1983.

My commission expires December 10, 1983

Mary Susan Whaley
Mary Susan Whaley Notary Public



RECEIVED
STATE CORPORATION COMMISSION

MAR 14 1983
03-14-83
CONSERVATION DIVISION
Wichita, Kansas

15095-213230000

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

Keener Oil Company
Kaw Drilling Co., Inc.
#1 Wilson
NW SE Sec. 9-28S-9W
Kingman County, Kansas
February 26, 1983
March 8, 1983

SPUD DATE:
COMPLETION DATE:

1397	1607	Shale and Shell
1607	1845	Shale
1982	2152	Shale and Shell
2310	2446	Shale
2446	2568	Shale and Lime
2848	2990	Shale and Lime
3686	3778	Shale and Lime
3962	4020	Shale and Lime
4081	4165	Shale and Lime
4233	4314	Lime
	4324	R.T.D.

Spud hole at 11:00 a.m. on February 26, 1983. Drilled 221 feet of 12 1/4 inch hole. Ran 206 feet of 8 5/8 inch casing. Set at 218 feet with 175 sacks of common cement, 3% Calcium Chloride and 2% Gel. Plug down at 4:00 p.m. on February 26, 1983.

Total Depth 4324 feet. Set first plug at 1150 feet with 40 sacks of common cement, 3% Calcium Chloride and 2% Gel; set second plug at 240 feet with 40 sacks; 10 sacks and a bridge at 40 feet and 10 sacks in the rathole. Job completed at 8:45 p.m. on March 8, 1983. State Plugger - Mr. Leslie


STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

RECEIVED
STATE CORPORATION COMMISSION

MAR 14 1983

CONSERVATION DIVISION
Wichita, Kansas

I, K. S. Martin, President of Kaw Drilling Co., Inc., being first duly sworn and upon my oath, state that: I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.


K. S. Martin, President

SUBSCRIBED AND SWORN to before me on this 11th day of March, 1983.


Mary Susan Whaley, Notary Public

My Commission Expires: December 10, 1983

