

15-095-00209-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Report an Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County, Sec. 11 Twp. 28 Rge. 9 (E) (W)

Location as "NE/CNW/SW" or footage from lines CE/2 NE NW

Lease Owner Bachus Oil Company

Lease Name Hay Well No. 1

Office Address 415-16 Union Center, Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7/8 1956

Application for plugging filed 9/24 1956

Application for plugging approved 9/24 1956

Plugging commenced 9/28 1956

Plugging completed 9/28 1956

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4520 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	260'	
				5 1/2"	4110'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Chat to 4000' run 5 sacks cement. Hole circulated with Jell Mud through 5 1/2" at free point. Mud to 250' set rock bridge. run 20 sacks cement. Mud to 35', set rock bridge, run 10 sacks cement cap. Mud pumped by Globe Cementing Co.

RECEIVED
STATE CORPORATION COMMISSION

OCT 18 1956

CONSERVATION DIVISION
Wichita, Kansas

10-01-56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Co.

Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Pat Yandell (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Pat Yandell

(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of October, 1956

My commission expires Jan. 31, 1957

My commission expires Notary Public.

PLUGGING
FILE SEC 11 T. 28 R. 9 W
BOOK PAGE 101 LINE 23

ROTARY DRILLING LOG

OPERATOR: Bachus Oil Company
Hay #1
C E/2 NE NW Sec. 11-28S-9W,
Kingman County, Kansas

CONTRACTOR: Prime Drilling Company
COMM: 7/8/56
COMP: 7/27/56

Remarks: Set 8-5/8" surface casing at
260' cemented with 215 sacks common
cement, 2% C.C.

Formations:

Sand & Clay	85'
Shale & Red Bed	300'
Shale & Shells	1250'
Anhydrite	1290'
Shale & Lime	2185'
Shale	2420'
Shale & Lime	3220'
Lime	3395'
Shale & Lime	3425'
Lime	3945'
Lime & Shale	4000'
Lime	4014'
Chert	4024'
Chert - Lime	4080'
Lime	4127'
Lime & Shale	4260'
Shale	4310'
Lime	4360'
Chert & Lime	4385'
Lime & Sand	4403'
Lime & Shale	4520'
Rotary Total Depth	4520'

Set 5-1/2" oil string casing at 4110' R.B.
cemented with 150 sacks common cement.

We certify the above log is true and
correct to the best of our knowledge
and belief.

PRIME DRILLING COMPANY

L. J. Clampitt
L. J. Clampitt

RECEIVED
STATE OF KANSAS
JUL 28 1956
CONSERVATION

PLUGGING
FILE SEC 11 T 28 R 9W
BOOK PAGE 101 LINE 23