

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-095-21793-0000
LEASE NAME Gillen
WELL NUMBER 1

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1980 Ft. from South Line of Section
1980 Ft. from East Line of Section

LEASE OPERATOR Messenger Petroleum, Inc. SPOT LOCATION C Nw Se
ADDRESS 525 S. Main Section 25 Township 28s Range 8W
CITY, STATE, ZIP Kingman, Kansas 67068 County Kingman
PHONE # 316-532-5400 Date Well Completed 08/24/01
Character of Well D&A Date Plugging Commenced 08/24/01
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 08/24/01

The plugging proposal was approved on August 24, 2001 at 11:00 am (date)
by Jack Luthi (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 4480

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	144			
Redbeds	Shale	144	300	8-5/8"	285.89'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged hole using 155 sx 60/40 Poz 4% Gel. Heavy in hole mud from 4480' to 1150'.

1st plug @ 1150' with 35sx, 2nd plug @ 750' with 35sx, 3rd plug @ 350' with 35sx, top plug @ 60'

with 25 sx from 60' to surface. Plugged mousehole with 10 sx and rathole with 15 sx. Job completed at

11:00 am on 8/24/01 by Allied. Ticket # 08731.

Name of Plugging Contractor Sterling Drilling Company

Licence No. 5142

Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Sterling Drilling Company (Agent)

STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.


(Signature) Gary M. Talbott
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 28th day of Aug. 2001

Pamela S. Fields

(Notary Public)



My Commission Expires:

RECEIVED

AUG 29 2001

KCC WICHITA

Form CP-4
Revised 12-92

OR

15-095-21793-0000

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

Gillen 1

LOCATION: C Nw Se
API: 15-095-21793-0000

Section 25 T 28s R 8w
Kingman County, Kansas

OWNER: Messenger Petroleum, Inc.
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 08/16/01
COMPLETED: 08/24/01

TOTAL DEPTH:	DRILLER	4480	FEET
	LOGGER	4482	FEET

Ground Elevation: 1619
KB Elevation: 1628

LOG

0 -	144 FEET	Top Soil and Water Sands
144 -	970 FEET	Redbeds
970 -	1550 FEET	Shales and Salt
1550	4480 FEET	Shale/Limestone/Chert and Sandstone

CASING RECORDS

Spud @ 8:45 am on 08-16-01. Drilled 12-1/4" hole to 300'. Ran 7 joints of new 20# 8-5/8" surface casing 285.89' set at 297' KB. Cemented with 185 sacks 60/40 Poz, 2% Gel, 3% CC. Plug down at 2:00 pm on 08-16-01 by Allied. Good returns. Ticket # 3477.

PLUGGING RECORDS

Plugged hole using 155 sx 60/40 Poz 4% Gel. Heavy in hole mud from 4480' to 1150'. 1st plug @ 1150' with 35sx, 2nd plug @ 750' with 35sx, 3rd plug @ 350' with 35sx, top plug @ 60' with 25 sx from 60' to surface. Plugged mousehole with 10 sx and rathole with 15 sx. Job completed at 11:00 am on 8/24/01 by Allied. Ticket # 08731.

DEVIATION SURVEYS

1/4	degree(s) at	300	feet
2	degree(s) at	4115	feet

RECEIVED
AUG 29 2001
KCC WICHITA