


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Kingman

County. Sec. 30 Twp. 28 Rge. 8 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Franco Central Oil Co.
Lease Name Rohlman Well No. 1
Office Address Fourth National Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed March 23 19 60
Application for plugging filed March 23 19 60
Application for plugging approved March 23 19 60
Plugging commenced March 23 19 60
Plugging completed March 23 19 60
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	267'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 240'
Set plug @ 240' with 1/4 sack of hulls.
Ran 15 sacks of cement through drill pipe. Set top plug at 40' with 10 sacks of cement.

STATE CORPORATION COMMISSION

MAR 25 1960 03-25-60

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Co.
Address Box 173 - Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
George A. Angle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle
580 4th National Bank Bldg. - Wichita
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of March, 1960

Marnie Head
Notary Public.

My commission expires 11-17-62



DRILLERS LOG

No. 1 Rohlman

CASING RECORD: 8 5/8" @ 264' w/250 sx cement
 COMPANY: Franco Central Oil Co.
 CONTRACTOR: Red Tiger Drilling Co.
 COMMENCED: March 4, 1960
 COMPLETED: March 23, 1960
 DESCRIPTION: NW NW SE 30-28S-8W Kingman County Kansas
 ELEVATION: 1664 DF 1667 RB
 TOTAL DEPTH: 4643'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Soil Sandy Clay	0	55	
Redbed	55	415	
Shale Shells	415	615	
Shale & Shells	615	1060	
Shale & Lime	1060	1350	
Lime & Shale	1350	2085	
Shale Lime	2085	2335	
Shale & Lime	2335	2585	
Lime & Shale	2585	2640	
Lime Shale	2640	2695	
Lime & Shale	2695	2880	
Lime Shale	2880	2945	
Lime	2945	3257	
Lime & Shale	3257	3360	
Lime	3360	4125	
Mississippi	4125	4140	
Mississippi Chert	4140	4155	
Chat	4155	4219	
Lime	4219	4355	
Lime & Shale	4355	4390	
Shale & Lime	4390	4450	
Lime Chert	4450	4480	
Lime & Shale (Cherty)	4480	4516	
Simpson	4516	4540	
Shale & Lime	4540	4567	
Lime	4567	4615	
Lime & Shale	4615	4643	

RECEIVED
 STATE CORPORATE COMMISSION

MAR 25 1960

CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING CO.

George A. Angle
 George A. Angle

Subscribed and sworn to before me this 23rd day of March, 1960.

Maxine Head
 Notary Public

My Commission Expires:

11-17-62