

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Kingman County, Sec. 32 Twp. 28 Rge. 8 (W)

Location as "NE/CNW/SW" or footage from lines SE SW NW

Lease Owner Aurora Gasoline Co. & Aylward Drilling Company

Lease Name Hibbs Well No. 1

Office Address 813 1st Natl. Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 31 19 55

Application for plugging filed October 31 19 55

Application for plugging approved October 31 19 55

Plugging commenced November 1 19 55

Plugging completed November 1 19 55

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives - Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4600 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	133'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 4600' to 130'; set plug at 130' with 20 sacks of cement; filled with heavy mud to 35'; filled from 35' to top of surface with 10 sacks of cement.

NOV 5 1955
11-05-55
DIVISION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Aylward Drilling Company

Address 813 1st Natl. Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Paul W. Hesse (employee of owner) or (owner or operator)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse

813 1st National Bank Bldg., Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of November, 1955

My commission expires December 11, 1957

Duane Jessup - Notary Public.

PLUGGING
FILE SEC 32 T 28 R 8 W
BOOK PAGE 13 LINE 18

HIBBS #1

Casing Record:

8-5/8" - 133' with 120 sacks

Company: Aylward Drilling Company & Aurora Gasoline Company

Contractor: Aylward Drilling Co.

Commenced: October 14, 1955

Completed: October 31, 1955

Elevation: 1610 D.F.
1612 K.B.

Location:
SE SW NW
Section 32-28-8W
Kingman County, Kansas

	From	To		Remarks
Sand & Shale	0	140	<u>D.S.T. #1</u>	3138-67- Open 30 minutes.
Red Rock	140	428		Recovered 2' mud. BHP 280#
Red Rock & Gray Shale	428	699		in 15 minutes.
Shale & Shell	699	830		
Shale & Shells	830	1343	<u>D.S.T. #2</u>	3245-66- Open 60 minutes.
Anhydrite	1343	1390		Recovered 1340' Muddy Salt
Lime & Shale	1390	2760		Water (No BHP recorded)
Sandy Lime & Shale	2760	2915		
Lime & Shale	2915	3118	<u>D.S.T. #3</u>	3798-3827- Open 60 minutes
Sand, Lime & Shale	3118	3167		Recovered 75' of very
Sand	3167	3183		slightly oil & gas cut
Lime, Sand & Shale	3183	3266		watery mud. BHP 690# in
Sand	3266	3296		20 minutes.
Sandy Lime & Shale	3296	3442		
Lime & Shale	3442	3483	<u>D.S.T. #4</u>	4081-90- Open 1 1/2 Hours.
Lime	3483	3752		Recovered 120' of Gas Cut
Lime & Shale	3752	3798		& Slightly Oily Cut Muddy
Lime	3798	3845		Salt Water. BHP 1410# in
Lime & Shale	3845	4090		30 minutes.
Cherty Mississippi	4090	4110		
Lime	4110	4183	<u>D.S.T. #5</u>	4090-4110-Open 90 minutes.
Lime & Shale	4183	4412		Recovered 490' Salt Water
Lime	4412	4414		BHP 1330# in 30 minutes.
Lime & Shale	4414	4463		
Lime & Sand	4463	4486	<u>D.S.T. #6</u>	4304-14- Open 120 minutes
Sand & Shale	4486	4536		Recovered 8' mud. BHP 1320#
Lime & Shale	4536	4566		in 20 minutes.
Lime & Shale	4566	4600	R.T.D.	

GEOLOGICAL TOPS:

Heebner	3202
Douglas Shale	3226
Douglas Sand	3244
Brown Lime	3421
Lansing K.C.	3433
Mississippi	4080
Kinderhook	4232
Viola	4404
Simpson Shale	4458
Simpson Sand	4487
Arbuckle	4557
R.T.D.	4600

RECEIVED
STATE CORPORATION COMMISSION
NOV - 5 1955
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse

Paul W. Hesse

Subscribed and sworn to before me this 4th day of NOVEMBER, 1955.

Duane Jessup

Duane Jessup
Notary Public

My Commission Expires: December 11, 1955

PLUGGING
BOOK PAGE 13 LINE 18