

15-095-00499-0000

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Kenneth Jones of Murfin Drilling Co. has this date requested permission to plug the following described well:

Mr. Jones guarantees payment of the plugging fee.

Operator's full Name: Whitney Operating Co.

Complete Address: 902 1st National Bldg., Tulsa, Oklahoma

Lease Name: Bryant Well No. # 1

Location: SE SW Sec. 36 Twp. 28 Rge. 8 (E) (W) W

County Kingman Total Depth 4531 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Jones was instructed to plug the well as follows:

272' of 8 5/8" surface pipe, cemented with 250 sacks.

Fill hole with drilling mud to 265', 1st cementing plug,

1/2 sack hulls, cement with 25 sacks. Fill hole with drill-

ing mud to 40', 2nd cementing plug, 1/2 sack hulls, cement

with 10 sacks to base cellar. Bridge and cement rat hole

with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent