

15-095-20021-0000

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 1 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed April 17, 1967.

Dear Sir:

Mr. Red Bishop of Leben Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. Bishop guarantees payment of the plugging fee.

Operator's full Name: Kaiser-Francis, Lario & Leben

Complete Address: 815 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Martha Simons Well No. # 1

Location: C NE NE Sec. 26 Twp. 28 Rge. 8 (E)(W) W

County Kingman Total Depth 4425' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bishop was instructed to plug the well as follows:

218' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill
hole with drilling mud to 220', bridge with 1/2 sack of hulls, and cement
with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug
bridge with 1/2 sack of hulls, and cement with 10 sacks to the base of
the cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Aubie Elving
Conservation Division Agent